DISTRICT BOARD, HASSAN.

Notification dated 25th July 1929.

Notice is hereby given that sealed tenders will be received at the Office of the President, District Board, Hassan, up to 2 P.M., on Monday the 5th August 1929, for constructing four blocks of out-houses, two for each block to the Rangacharlu Chattram at Arsikere. Tenders will be received separately for each block.

Approximate quantities are given below. The quantities are not guranteed. The work should be completed by the end of November 1929.

The plan and estimate may be seen at the President's Office at Hassan between the hours of 11 A.M. and 5 P.M. on all working days.

Each tender should be accompanied by a statement in the form given below showing the rates at which the different items specified will be executed.

Each tender must be accompanied by a deposit of Rs. 100 only in cash or Government Promissory Notes as earnest money, and be superscribed "Tenders for constructing a block of out-house to the Rangacharlu Chattram at Arsikere" in default of which, tenders will be rejected. The final acceptance of any tender will rest with the President, District Board, Hassan, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender. Within eight days of the acceptance of the tender, the successful tenderer will be required to execute the usual contract bond, in default of which his tender will be considered cancelled and his earnest money will be forfeited.

The name of the successful competitor whose tender has been accepted will be posted on the notice board in the President's Office in due course.

No enquiries regarding the acceptance or rejection of a tender will receive any reply.

On acceptance of one of the tenders the earnest money on rejected tenders will be returned.

Abstract for the construction of out-houses to the Rangacharlu Chattram at Arsikere.

Serial No.	Details of work	Quantity	Per	Rate	Cost
1	Excavation for foundation hard soil ...	19—7/9	C.yd.	Rs.	Rs.
2	Filling foundation rough stone in mud ...	534	C.ft.		
3	Basement burnt stone in chunam ...	302	„		
4	Burnt brick in clay	1,119	„		
5	Honne or Nandiwood doors and windows ...	68	S.ft.		
6	Burnt stone slabs dressed 6" thick ...	91	„		
7	Honne or Nandi wood work	30·09	C.ft.		
8	Chunam plastering	24·00	Sqr.		
9	Whitewashing	24·00	„		
10	Roofing with Mangalore tiles (first class) ...	6·82	„		
11	New ridge tiles set in mortar ...	31	R.ft.		
12	Smoke tiles or chmimney*	6	...		
		1	..		
13	Jelly concrete for flooring and plastering with cement.	1·08	Sqr.		
14	Chocolate painting	1·36	„		
15	Construction of cistern with cudapah slab bottom.	2	L.S.		
16	Chunam borders 9" thick	40	R.ft.		
17	Contingencies at 5 per cent	...	...		

N. S. NANJUNDIAH,
President.